



INVICTUS®

GREAT FLOORING · INVINCIBLE PERFORMANCE



LUXURY VINYL FLOORING



INVICTUS®

Great Flooring, Invincible Performance

When it comes to delivering a great performance, nothing beats Invictus® luxury vinyl flooring. The name is no coincidence: in Latin, “invictus” means “invincible”. Invictus® luxury vinyl flooring is sure to meet all your expectations.

Your Invictus® luxury vinyl floor will be a striking style feature in your home. Choose from a large variety of designs – including true-to-nature wood planks and realistic stone look tiles, or make a bold statement with an intricate pattern.

Invictus® exclusively benefits from Scratchmaster®. This top layer will make your luxury vinyl floor withstand busy family life with kids and pets.

The planks and tiles of Invictus® are easy to handle and install, extremely wear-resistant and require little maintenance.

Invictus® is waterproof and therefore never out of place, not even in your kitchen, bathroom or hall.

Invictus® contributes to creating a relaxing environment. It is silent underfoot and greatly improves the acoustic qualities of your home.

Free sample request
www.invictus.co.uk



DISCOVER INVICTUS®

The strengths of Invictus®	6	Why Invictus® Rigid Click?	68
Overview collection	8	Maximus® Click collection	70
Wood Planks	8	Highland Oak	72
Parquet Planks	10	French Oak	74
Stone Tiles	11	Norwegian Wood	76
		Groovy Granite	78
Get inspired	12	Matching scotias	80
Commercial use	14	Feature strips	82
Why Invictus® Dryback?	18	Installation	84
Maximus® collection	20	Cleaning & Maintenance	85
New England Oak	22	Laying patterns	86
Highland Oak	24	Social Media & Website	88
Tropical Forest	26	Shop-in-shop & Shop locator	90
French Oak	28	Warranties	92
Norwegian Wood	30	Technical specs	93
Highland Oak Parquet	32	Overview strengths	100
New England Oak Parquet	34	Invictus® carpet	102
Designers Parquet	36	Matching carpets	104
Hudson Stone	38	About Associated Weavers	106
Bergamo	40		
Terrazzo Time	42		
Groovy Granite	44		
Belgian Bluestone	46		
Victorian Treasure	48		
Concrete Crush	50		
Primus® collection	52		
Royal Oak	54		
Sherwood Oak	56		
Vintage Oak	58		
Royal Oak Parquet	60		
Pure Marble	62		
York Stone	64		
Sandstone	66		

Invictus®, the award-winning brand!



Voted best brand, best website and best shop display by the flooring trade and trade press.

THE STRENGTHS OF INVICTUS® LUXURY VINYL FLOORING

Invictus® luxury vinyl flooring offers nothing but invincible benefits. It will meet all that you expect of a great floor, delivering on all the important characteristics.

On top of these benefits, some Invictus® luxury vinyl floors have specific features. Find out more on these features on the product pages and let them guide you towards the best fitted floor for your home. All technical specifications are also available on the website www.invictus.co.uk.



Invictus® luxury vinyl flooring products are 100% recyclable and reusable. They can be part of vinyl flooring take-back programmes with the goal to recycle them into new flooring or other useful products such as rubber hoses, car mats and speed bumps.



Invictus® luxury vinyl flooring is a family's best companion. It's hygienic, wear-, scratch- & stain-resistant, and requires little maintenance.



Invictus is the pet friendly flooring par excellence, operating as a barrier against stains and fine scratches from our furry friends.



Because it's waterproof, Invictus® luxury vinyl flooring is perfectly suited for your bathroom, kitchen and hall. And for any other room, naturally.



Caring for your Invictus® luxury vinyl floor is as easy as it gets: a damp mop will do. And for daily maintenance, the Invictus® Starter Pack contains all you need.

Free sample request
www.invictus.co.uk



With its ultra-strong coating and highly efficient top layer, Invictus® luxury vinyl flooring offers outperforming wear protection. The Scratchmaster® top layer will make your luxury vinyl floor withstand busy family life with kids and pets.



Invictus® luxury vinyl flooring and broadloom carpet are a perfect match. When great comfort meets great performance, it will transform your home.



Invictus® luxury vinyl flooring and underfloor heating go together well. With the right installing guidelines, you'll be enjoying a warm feel underfoot in no time.



Invictus® Primus performs so well, that it comes with a 20-year residential warranty. Invictus® Maximus and Maximus Click deliver an extraordinary performance and benefit from a 25-year warranty.



Designs so lifelike, they will have you look twice. From natural wood look to striking stone tile pattern, there's an Invictus® luxury vinyl floor for all decorating styles.



Whether on socks or in shoes, you will always walk silently on an Invictus® luxury vinyl floor. It indeed is incredibly silent underfoot.



What's better than unwinding in the tranquility of your own home? Your Invictus® luxury vinyl floor contributes to a silent and relaxing environment.

Overview Wood Planks



Royal Oak Eden (p.55)

Primus



Norwegian Wood Arctic (p.31 & 77)

Maximus + Click



French Oak Polar (p.29 & 75)

Maximus + Click



French Oak Linen (p.29 & 75)

Maximus + Click



Sherwood Oak Fossil (p.57)

Primus



Sherwood Oak Shell (p.57)

Primus



Tropical Forest Aruba (p.27)

Maximus



French Oak Desert (p.29 & 75)

Maximus + Click



Designers Parquet Princess (p.37)

Maximus



Royal Oak Blonde (p.55)

Primus



Designers Parquet Duchess (p.37)

Maximus



Designers Parquet Queen (p.37)

Maximus



New England Oak Sand (p.23)

Maximus



Highland Oak Roasted (p.25 & 73)

Maximus + Click



Highland Oak Classic (p.25 & 73)

Maximus + Click



Tropical Forest Havana (p.27)

Maximus



French Oak Sun (p.29 & 75)

Maximus + Click



Vintage Oak Café au Lait (p.59)

Primus



Royal Oak Traditional (p.55)

Primus



Sherwood Oak Mink (p.57)

Primus



Highland Oak Canyon (p.25 & 73)

Maximus + Click



New England Oak Dusk (p.23)

Maximus




Tropical Forest Peru (p.27)

Maximus



French Oak Almond (p.29 & 75)

Maximus + Click



Royal Oak Nordic (p.55)

Primus



Royal Oak Dove (p.55)

Primus



French Oak Storm (p.29 & 75)

Maximus + Click




New England Oak Misty (p.23)

Maximus



Norwegian Wood Fjord (p.31 & 77)

Maximus + Click



Highland Oak Frosted (p.25 & 73)

Maximus + Click



Highland Oak Ash (p.25)

Maximus



Norwegian Wood Thunder (p.31 & 77)

Maximus + Click



French Oak Burnt (p.29 & 75)

Maximus + Click




Highland Oak Ebony (p.25)

Maximus



Highland Oak Chocolate (p.25 & 73)

Maximus + Click



Norwegian Wood Barrel (p.31 & 77)

Maximus + Click



New England Oak Toffee (p.23)

Maximus



Royal Oak Mocca (p.55)

Primus

Overview Parquet Planks



Highland Oak Ebony (p.33)



Royal Oak Nordic (p.61)



Highland Oak Frosted (p.33)



Highland Oak Chocolate (p.33)



New England Oak Toffee (p.35)



New England Oak Dusk (p.35)



Highland Oak Roasted (p.33)



Royal Oak Traditional (p.61)



Highland Oak Classic (p.33)



New England Oak Sand (p.35)



New England Oak Misty (p.35)



Royal Oak Dove (p.61)




Highland Oak Canyon (p.33)


Overview Stone Tiles



Concrete Crush Charcoal (p.49 & 51)




Hudson Stone Graphite (p.39)




Groovy Granite Lava (p.45 & 79)




Belgian Bluestone Midnight (p.41)



Belgian Bluestone Dolphin (p.41)



Groovy Granite Steel (p.45 & 79)



Sandstone Nero (p.65)



Hudson Stone Flint (p.39)



Sandstone Savannah (p.65)




Groovy Granite Shadow (p.45 & 79)




Concrete Crush Smoke (p.49 & 51)




Groovy Granite Dune (p.45 & 79)



Hudson Stone Silver (p.39)




Bergamo Cloud (p.41)



Terrazzo Time Taupe (p.43)



York Stone Powder (p.65)



Pure Marble Snow (p.63)

Victorian Treasure



Border - Smoke (p. 49)



Decor - Smoke (p. 49)



Border - Charcoal (p. 49)



Decor - Charcoal (p. 49)

GET INSPIRED

Whatever your decorating style, there's an Invictus® luxury vinyl floor for every home, from contemporary to country, from traditional townhouse to urban loft. Choose your preferred style and let it guide you towards the floor that is just right for you.

For more inspiration, use the Room Visualiser on www.invictus.co.uk



CONTEMPORARY DESIGN

Modern, eclectic and always on trend.



TOWNHOUSE

Grand, traditional and throughout classy.



COUNTRY LIVING

Natural, cosy and truly authentic.



URBAN

Sleek, sophisticated and bringing cool vibes.

Follow us on social media
[@invictuscarpetflooring](https://www.instagram.com/invictuscarpetflooring)
[#invictuscarpetflooring](https://www.facebook.com/invictuscarpetflooring)



JOIN OUR INVICTUS® COMMUNITY

Get inspired by our community of Invictus® fans. Visit www.invictus.co.uk/lvt/community

Want to join the Invictus® community? Tag [@invictuscarpetflooring](https://www.instagram.com/invictuscarpetflooring) in your Invictus® luxury vinyl flooring photo on Instagram and use [#invictuscarpetflooring](https://www.instagram.com/invictuscarpetflooring) for a chance to get featured! More info on p.88-89.



INVICTUS® LUXURY VINYL FLOORING: THE IDEAL CHOICE FOR COMMERCIAL USE

For commercial purposes as well, Invictus® luxury vinyl flooring is the ideal choice. Designed to withstand even the heaviest commercial use – such as care, hospitality, office and retail environments – Invictus® Maximus and Maximus Click are sure to fulfill all technical requirements. For your safety, Invictus® comes in a number of 36+ slip resistant planks and tiles.



RETAIL

In your shop, the floor has just one part to play: creating the perfect setting for your carefully chosen collection to shine. Invictus® luxury vinyl flooring is happy to contribute to your sales success. With near-limitless design options, colours and laying patterns, there's always an Invictus® floor to complement the look and feel of your brand. And you'll certainly also appreciate the durability and easy maintenance of Invictus®.



CARE

For all ages and all needs: care means comfort. Trust Invictus® flooring to be up to the task, from calming the atmosphere at a health spa or creating a safe environment for the elderly, to safeguarding youngsters playing without a care in the world. Invictus® luxury vinyl flooring is durable, slip resistant, silent underfoot and easy to care for. Plenty of qualities sure to give you the peace of mind to focus on what counts for you: caring for your guests.





OFFICE

In office spaces, the floor has to keep up with everyone's busy schedule. Teams gather for brainstorming sessions; clean desks inspire creativity and "aha" moments occur naturally in the coffee corner. Invictus® luxury vinyl flooring will be a stalwart silent witness to it all. It's silent underfoot for a tranquil working environment, slip resistant, easy to maintain and exceptionally durable thanks to the Scratchmaster® wear protection.




HOSPITALITY

When dining out or spending a weekend at a B&B, the experience is everything. You want to offer your guests an unforgettable moment away from it all. There are plenty Invictus® designs to complement your chosen concept, from country haven to urban sophistication. Or choose an intricate laying pattern for that extra touch of exclusivity. As a hospitality expert, you will also appreciate the wear resistance and easy maintenance of Invictus® luxury vinyl flooring.



WHICH INVICTUS® LUXURY VINYL FLOOR SHOULD I CHOOSE?

Invictus® luxury vinyl flooring has many options to choose from, in three ranges: Invictus® Primus, Maximus and Maximus Click. The best choice for your home? It all depends on both your design dreams and installing preferences.



INVICTUS® PRIMUS AND MAXIMUS ARE DRYBACK LUXURY VINYL FLOORINGS

Invictus® Dryback luxury vinyl flooring comes in two ranges:

- 1 **Invictus® Primus** stands for luxury vinyl planks and tiles with a wear layer of 0.30mm. They offer excellent value for money and are designed to effortlessly withstand the challenges of daily family life.
- 2 **Invictus® Maximus** consists of luxury vinyl planks and tiles with a wear layer of 0.55mm. They offer excellent wear resistance and durability, which makes them suited even for heavy commercial use such as care, hospitality, office and retail.

The advantages of Invictus® Dryback luxury vinyl flooring:

- ✓ It is the professional installer's premium choice. Whether consisting of wood design planks or stone look tiles, Dryback flooring will offer a superb performance for many years to come. The floor is glued directly to the subfloor, resulting in exceptional dimensional stability.
- ✓ No decorating wish remains unfulfilled: create original patterns or add embellishments like feature strips for a tone-on-tone or contrasting grout effect. The result is a stunning floor in either wood or stone design, that will have you look twice.
- ✓ Dryback flooring is the ideal solution for installing on top of an existing floor. Installation of the planks and tiles on a leveled floor is easy, dust free and does not require the use of specialized tools: a utility knife is all you need. And no need to adapt the doors: because of its limited thickness, your new floor will easily fit underneath.

Full details on Invictus® Rigid Click on page 68.



MAXIMUS® COLLECTION

Invictus® Maximus consists of luxury vinyl planks and tiles with a wear layer of 0.55mm. They offer excellent wear resistance and durability, which makes them suited even for heavy commercial use such as care, hospitality, office and retail.



More information about Invictus® strengths on pages 6 and 100.



Infinite repeat
The extra large design results in minimal pattern repetition, giving a truly unique & natural look to any space.

New England Oak

Oak design luxury vinyl planks for a breezy, relaxed look.
A variegated oak pattern in soft and subtle colours.

178 x 1219mm / 7" x 48"
15 planks / carton = 3.25 m² (35 ft²) / carton



Toffee VDNWE5A45018122P15



Sand VDNWE5A32018122P15



Misty VDNWE5A93018122P15



Dusk VDNWE5A40018122P15

- scratchmaster[®]
outperforming wear protection
- 25 year warranty
- 15 year commercial warranty
- infinite repeat



MAXIMUS - New England Oak - Toffee - Laying Pattern: Brick Formation

Free sample request
www.invictus.co.uk

Highland Oak

Oak design luxury vinyl planks that take you to the summit of style.
A remarkable oak pattern in rustic colours.

178 x 1219mm / 7" x 48"
15 planks / carton = 3.25 m² (35 ft²) / carton




Classic VDHIG5A33018122P15



Roasted VDHIG5A34018122P15




Chocolate VDHIG5A42018122P15




Ash VDHIG5A94018122P15



Ebony VDHIG5A99018122P15



Frosted VDHIG5A91018122P15



Canyon VDHIG5A39018122P15



Tropical Forest


Luxury vinyl planks with a lush and exotic vibe.
A rustic banana tree leaf pattern in subtle shades.

178 x 1219mm / 7" x 48"
15 planks / carton = 3.25 m² (35 ft²) / carton



Havana

VDTRO5A38018122P15



Aruba

VDTRO5A30018122P15



Peru

VDTRO5A39018122P15



MAXIMUS - Tropical Forest - Havana - Laying Pattern: Brick Formation

In register embossing follows the wood design of your floor, thus giving it depth and an exceptionally realistic look.



French Oak

Oak design luxury vinyl planks with a dash of understated class. A limed oak pattern in soft colours.

178 x 1219mm / 7" x 48"
15 planks / carton = 3.25 m² (35 ft²) / carton



Polar VDFRE5R03018122P15



Linen VDFRE5R30018122P15




Desert VDFRE5R33018122P15



Sun VDFRE5R38018122P15



Almond VDFRE5R37018122P15



Burnt VDFRE5R98018122P15



Storm VDFRE5R92018122P15





In register embossing follows the wood design of your floor, thus giving it depth and an exceptionally realistic look.

Norwegian Wood

Pine design luxury vinyl planks with a striking character.
A rustic pine pattern in multicoloured tones.

178 x 1219mm / 7" x 48"
15 planks / carton = 3.25 m² (35 ft²) / carton



Barrel VDNOR5R42018122P15



Fjord VDNOR5R39018122P15



Thunder VDNOR5R49018122P15



Arctic VDNOR5R09018122P15






Highland Oak Parquet

Oak design luxury vinyl parquet that takes you to the peak of style.
Go for bold with a herringbone pattern in rustic oak shades.

102 x 406mm / 4" x 16"
34 planks / carton = 1.40 m² (15.11 ft²) / carton



Ebony
VDNWE5A40010041P34



Frosted
VDHIG5A91010041P34



Canyon
VDHIG5A39010041P34



Chocolate
VDHIG5A42010041P34



Roasted
VDHIG5A34010041P34



Classic
VDHIG5A33010041P34

MAXIMUS - Highland Oak Parquet - Chocolate - Laying Pattern: Herringbone



For more inspiration, use the Room Visualiser on www.invictus.co.uk



New England Oak Parquet

Oak design luxury vinyl parquet for a breezy, relaxed look. A wood block pattern adds a creative touch to the soft and subtle colours.

102 x 406mm / 4" x 16"
34 planks / carton = 1.40 m² (15.11 ft²) / carton



Dusk VDNWE5A40010041P34 Misty VDNWE5A93010041P34 Sand VDNWE5A32010041P34 Toffee VDNWE5A45010041P34



In register embossing follows the wood design of your floor, thus giving it depth and an exceptionally realistic look.




Designers Parquet

Designers Parquet with an attractive pattern that exudes grandeur. A modern approach to a classic wood design.

229 x 1517mm / 9" x 60"
10 planks / carton = 3.47 m² (37.33 ft²) / carton



Queen VDDPQ5R38023152P10



Duchess VDDPQ5R34023152P10



Princess VDDPQ5R30023152P10

- scratchmaster[®]
outperforming wear protection
- 25 year warranty
- 15 year commercial warranty
- embossed in register
- XL planks



Free sample request
www.invictus.co.uk



MAXIMUS - Hudson Stone - Silver - Laying Pattern: Brick Bond


Hudson Stone

Stone design luxury tiles that look stunningly natural.
An appealing stone design with distinctive, bright veins.

305 x 610mm / 12" x 24"
18 tiles / carton = 3.34 m² (36 ft²) / carton



Silver VDHUS5A91031061P18



Graphite VDHUS5A97031061P18



Flint VDHUS5A96031061P18






Free sample request
www.invictus.co.uk

Bergamo

Stone design luxury tiles that suit both classic and contemporary styles.
A granite design in harmoniously contrasting tones of grey.

457x914 mm / 18"x36"
8 tiles / carton = 3.34 m² (36 ft²) / carton



Cloud

VDBER5A94046091P08






Free sample request
www.invictus.co.uk

Terrazzo Time

Stone design luxury tiles for the vanguard of the terrazzo revival.
A stand-out stone design that encourages eclectic choices.

305 x 610mm / 12" x 24"
18 tiles / carton = 3.34 m² (36 ft²) / carton



Taupe

VDTER5A39031061P18




Groovy Granite

Stone design luxury vinyl tiles echoing the natural nuances of granite.
The distinctive character of granite in greys and beiges.


457 x 457mm / 18"x18"
16 tiles / carton = 3,34 m² (36 ft²) / carton

305 x 610mm / 12" x 24"
18 tiles / carton = 3,34 m² (36 ft²) / carton





Dune
VDGRA5A31046046P16

Dune
VDGRA5A31031061P18




Shadow
VDGRA5A39046046P16

Shadow
VDGRA5A39031061P18



Steel
VDGRA5A92046046P16

Steel
VDGRA5A92031061P18



Lava
VDGRA5A98046046P16

Lava
VDGRA5A98031061P18



MAXIMUS - Groovy Granite - Dune - Laying Pattern: Uniform Block

Free sample request
www.invictus.co.uk

Belgian Bluestone


Stone design luxury vinyl tiles with a nearly plain look.
A delicate stone pattern with a hint of blue.

500 x 500mm / 19.69" x 19.69"
14 tiles / carton = 3.50 m² (37.67 ft²) / carton



Dolphin

VDBLU5A95050050P14



Midnight

VDBLU5A97050050P14



Inspired by handmade cement tiles! True to the original artisan version, each Victorian tile is a little different. Your ultimate statement floor!



MAXIMUS - Victorian Treasure Decor - Charcoal - With matching border Concrete Crush - Charcoal

Victorian Treasure

Stone design luxury vinyl tiles for a vintage cement tile look. A classy statement floor, alone or with matching borders.

229 x 229mm / 9"x9"
40 tiles / carton = 2.09 m² (22.50 ft²) / carton



Border - Smoke
VDVBO5A96023023P40



Decor - Smoke
VDVDE5A96023023P40



Border - Charcoal
VDVBO5A99023023P40



Decor - Charcoal
VDVDE5A99023023P40

perfect match with:


Concrete Crush

Stone design luxury vinyl tiles for a full blown exposed concrete look. A modern plain tile design in a light or dark tone.

305 x 610mm / 12" x 24"
18 tiles / carton = 3.34 m² (36 ft²) / carton



Smoke
VDCON5A96031061P18



Charcoal
VDCON5A99031061P18



For more inspiration, use the Room Visualiser on www.invictus.co.uk




Concrete Crush

Stone design luxury vinyl tiles for a full blown exposed concrete look. A modern plain tile design in a light or dark tone.

305 x 610mm / 12" x 24"
18 tiles / carton = 3.34 m² (36 ft²) / carton




Smoke VDCON5A96031061P18



Charcoal VDCON5A99031061P18



MAXIMUS - Concrete Crush - Smoke - Laying Pattern: Brick Bond



PRIMUS[®] COLLECTION

Invictus[®] Primus stands for luxury vinyl planks and tiles with a wear layer of 0.30mm. They offer excellent value for money and are designed to effortlessly withstand the challenges of daily family life.



More information about Invictus[®] strengths on pages 6 and 100.

Infinite repeat
 The extra large design results in minimal pattern repetition, giving a truly unique & natural look to any space.



Royal Oak

Oak design luxury vinyl planks for a grand, majestic look.
 An authentic oak pattern in shades of brown and grey.

178 x 1219mm / 7" x 48"
 17 planks / carton = 3.69 m² (39.67 ft²) / carton




Blonde VDROY3A33018122P17



Traditional VDROY3A34018122P17




Mocca VDROY3A40018122P17



Dove VDROY3A93018122P17



Eden VDROY3A90018122P17



Nordic VDROY3A91018122P17




For more inspiration, use the Room Visualiser on www.invictus.co.uk

Sherwood Oak

Oak design luxury vinyl planks that make your home legendary.
A natural oak pattern with a subtle design.


178 x 1219mm / 7" x 48"
17 planks / carton = 3.69 m² (39.67 ft²) / carton



Fossil VDSHW3A90018122P17



Mink VDSHW3A40018122P17



Shell VDSHW3A30018122P17



Free sample request
www.invictus.co.uk

Vintage Oak

Oak design luxury vinyl planks in shades of beige for a rustic look.
 An unusual oak pattern with a weathered aspect.

178 x 1219mm / 7" x 48"
 17 planks / carton = 3.69 m² (39.67 ft²) / carton



Café au Lait

VDVIN3A39018122P17




For more inspiration, use the Room Visualiser on www.invictus.co.uk


Royal Oak Parquet

Oak design luxury vinyl parquet for a grand, majestic look. A herringbone pattern will make the authentic design stand out.

102 x 406mm / 4" x 16"
36 planks / carton = 1.49 m² (16 ft²) / carton



Dove
VDROY3A93010041P36



Nordic
VDROY3A91010041P36




Traditional
VDROY3A34010041P36



Pure Marble

Stone design luxury vinyl tiles that are fashionable and timeless in one.
A marble stone design that makes a big impression.

305 x 610mm / 12" x 24"
20 tiles / carton = 3.72 m² (40 ft²) / carton



Snow

VDPMA3A01031061P20



York Stone

Stone design luxury vinyl tiles with a classy crystalline shimmer.
A true to life stone design that shines naturally.

305 x 610mm / 12" x 24"
20 tiles / carton = 3.72 m² (40 ft²) / carton



Powder

VDYOS3A31031061P20



PRIMUS - York Stone - Powder - Laying Pattern: Brick Bond





Free sample request
www.invictus.co.uk


Sandstone

Stone design luxury vinyl tiles with an intriguing, speckled aspect.
 A mineral stone design that blends with all decorating styles.

305 x 610mm / 12" x 24"
 20 tiles / carton = 3.72 m² (40 ft²) / carton



Savannah VDSAS3A39031061P20



Nero VDSAS3A96031061P20




WHICH INVICTUS® LUXURY VINYL FLOOR SHOULD I CHOOSE?

Invictus® luxury vinyl flooring has many options to choose from, in three ranges: Invictus® Primus, Maximus and Maximus Click. The best choice for your home? It all depends on both your design dreams and installing preferences.



PRODUCT COMPOSITION

Rigid core SPC vinyl flooring with sound insulating underlay attached



INVICTUS® MAXIMUS CLICK IS A RIGID CLICK LUXURY VINYL FLOORING

Invictus® Maximus Click is luxury vinyl flooring to be installed using the click system. The outstanding rigid material of Invictus® Maximus Click is a far cry from seemingly similar but lesser quality products, and therefore guarantees an unseen level of dimensional stability.

Full details on Invictus® Dryback on page 18.

The advantages of Invictus® Maximus Click luxury vinyl flooring:

- ✓ Thanks to its high locking strength and dimensional stability, it is a favourite with professional installers and DIY enthusiasts alike. The click system makes the rigid wood design planks and stone look tiles easy to install – and to remove, should you wish to reuse your floor elsewhere. Installation does not require the use of specialized tools: a utility knife is all you need.
- ✓ With Invictus® Maximus Click planks or tiles, preparing the subfloor is superfluous. The rigid material is very forgiving and will hide tile joints and most imperfections such as cracks and high and low spots. The result is a perfectly smooth surface.
- ✓ Invictus® Maximus Click has an attached underlay, that enhances the acoustic benefits of your floor. On top of that, the underlay helps even out subfloor imperfections.
- ✓ Invictus® believes in sustainability: Maximus Click planks and tiles contain more than 20% of recycled production waste, reducing the need for raw materials
- ✓ There's a 100% matching scotia for each Invictus® Maximus Click design. Each scotia is made with the same luxury vinyl flooring material as used for the planks and tiles, resulting in a perfect colour match. It will not only cover the necessary expansion gap but also adds an elegant finishing touch.



MAXIMUS CLICK® COLLECTION

Invictus® Maximus Click consists of luxury vinyl planks and tiles with a wear layer of 0.55mm to be installed using the click system. They offer excellent wear resistance and durability, which makes them suited even for heavy commercial use such as care, hospitality, office and retail.

The outstanding rigid material of Invictus® Maximus Click is a far cry from seemingly similar but lesser quality products, and therefore guarantees an unseen level of dimensional stability.

- 25 year warranty
- 15 year commercial warranty
- family friendly
- pet friendly
- water proof
- easy maintenance
- silent underfoot
- underfloor heating
- bevel
- quick & easy
- 100% matching scotias
- no subfloor preparation

More information about Invictus® strengths on pages 6 and 100.

For more inspiration, use the Room Visualiser on www.invictus.co.uk



MAXIMUS CLICK - Highland Oak - Frosted - Laying Pattern: Random Lay

Highland Oak

Oak design luxury vinyl planks that take you to the summit of style.
A remarkable oak pattern in rustic colours.


178 x 1213mm / 7" x 47.75"
8 planks / carton = 1.725 m² (18.57 ft²) / carton




Classic VRHIG5A33018121P08



Roasted VRHIG5A34018121P08



Chocolate VRHIG5A42018121P08



Canyon VRHIG5A39018121P08



Frosted VRHIG5A91018121P08



In register embossing follows the wood design of your floor, thus giving it depth and an exceptionally realistic look.



MAXIMUS CLICK - French Oak - Almond - Laying Pattern: Brick Formation

French Oak

Oak design luxury vinyl planks with a dash of understated class.
A limed oak pattern in soft colours.

178 x 1213mm / 7" x 47.75"
8 planks / carton = 1.725 m² (18.57 ft²) / carton



Almond VRFRE5R37018121P08



Polar VRFRE5R03018121P08




Linen VRFRE5R30018121P08



Desert VRFRE5R33018121P08



Sun VRFRE5R38018121P08



Burnt VRFRE5R98018121P08



Storm VRFRE5R92018121P08





In register embossing follows the wood design of your floor, thus giving it depth and an exceptionally realistic look.

Norwegian Wood

Pine design luxury vinyl planks with a striking character. A rustic pine pattern in multitone colours.

178 x 1213mm / 7" x 47.75"
8 planks / carton = 1.725 m² (18.57 ft²) / carton



Barrel VRNOR5R42018121P08



Fjord VRNOR5R39018121P08



Thunder VRNOR5R49018121P08




Arctic VRNOR5R09018121P08



Groovy Granite

Stone design luxury vinyl tiles echoing the natural nuances of granite.
The distinctive character of granite in greys and beiges.


298 x 603mm / 11.75" x 23.75"
8 tiles / carton = 1.440 m² (15.503 ft²) / carton




Dune VRGRA5A31030060P08



Steel VRGRA5A92030060P08



Shadow VRGRA5A39030060P08



Lava VRGRA5A98030060P08



MAXIMUS CLICK - Groovy Granite - Shadow - Laying Pattern: Brick Bond

Now
also available
in paintable white,
to match your wall.



VAWHISC00018118P08

MATCHING SCOTIAS

There's a **100% matching scotia** for each Invictus® Maximus Click design. Each scotia is made with the same luxury vinyl flooring material as used for the planks and tiles, resulting in a perfect colour match. It will not only cover the necessary expansion gap but also add an elegant finishing touch.

Scotia size 1180 x 18mm - 8 pcs/pack = 9.44 lm



Almond
VAFRESC37018118P08



Arctic
VANORSC09018118P08



Barrel
VANORSC42018118P08



Burnt
VAFRESC98018118P08



Canyon
VAHIGSC39018118P08



Chocolate
VAHIGSC42018118P08



Classic
VAHIGSC33018118P08



Desert
VAFRESC33018118P08



Dune
VAGRASC31018118P08



Fjord
VANORSC39018118P08



Frosted
VAHIGSC91018118P08



Lava
VAGRASC98018118P08



Linen
VAFRESC30018118P08



Polar
VAFRESC03018118P08



Roasted
VAHIGSC34018118P08



Shadow
VAGRASC39018118P08



Steel
VAGRASC92018118P08



Storm
VAFRESC92018118P08



Sun
VAFRESC38018118P08








Thunder
VANORSC49018118P08

FEATURE STRIPS

Invictus® luxury vinyl flooring comes with optional feature strips that leave no decorating wish unfulfilled. Choose tone-on-tone feature strips to add an elegant touch to the floor pattern. Or embellish your luxury vinyl floor with contrasting feature strips for an eye-catching effect. The result is a stunning floor in either wood or stone design, that will have you look twice.



Feature strip size 1000 x 3mm - 30pcs/pack

	Charcoal	VASTRIP99003100P30
	Rhino	VASTRIP95003100P30
	Oyster	VASTRIP90003100P30
	Cream	VASTRIP31003100P30
	White	VASTRIP01003100P30

Feature strip size 1000 x 7mm - 25pcs/pack

	Blonde	VASTRIP33007100P25
	Mocca	VASTRIP40007100P25
	Black	VASTRIP98007100P25



INSTALLING YOUR INVICTUS® LUXURY VINYL FLOOR

No hassle, no waiting time ... Installing Invictus® luxury vinyl flooring is quick and easy, and dust free on top of that. The best guarantee for an impeccable Invictus® floor is to have it installed by a professional. Your preferred retailer will be glad to advise you and will make sure that the appropriate installing conditions are met. If you wish to rely on your own DIY skills, choose Invictus® Maximus Click.

Before installing Invictus® luxury vinyl flooring:

- ✓ With Invictus® Primus or Maximus, it is crucial to check the condition of the subfloor. Cracks should be filled, and bumps sanded. Another option is to install a plywood underfloor to obtain a perfectly even surface. When installing Invictus® Maximus Click, you may skip the preparation of the subfloor. The rigid click planks or tiles will hide tile joints and most imperfections.
- ✓ For commercial use, you may enhance the inherent acoustic benefits of your Invictus® Maximus floor with an extra underlay. No need for an underlay with Invictus® Maximus Click: it already has an underlay attached to the planks and tiles.
- ✓ Allow 24 hours for the Invictus® planks or tiles to acclimate before installation. Stack the packs horizontally on top of each other in the room the floor will be installed in.
- ✓ When installing Invictus® flooring on underfloor heating, please refer to the technical information sheet for detailed instructions.

Installing Invictus® luxury vinyl flooring:

- ✓ Mixing planks or tiles from different packs is your best guarantee for a harmonious look in design and colour on the entire floor.
- ✓ Invictus® Primus and Maximus are Dryback floors, to be glued down. Your retailer will select the best fitted glue for your floor.
- ✓ Invictus® Maximus Click planks and tiles are rigid and have an integrated click system, for easy installing without the use of any adhesives. Because it is a floating floor, you should allow an expansion gap of 5/16" near all walls. A 100% matching scotia glued to the wall will cover the gap.

INVICTUS® STARTER PACK

Keep your Invictus® luxury vinyl floor in mint condition



All you need to keep your Invictus® luxury vinyl floor in mint condition for years to come, is one small box: **The Invictus® Starter Pack.**

Right after installing

You may want to unpack the Starter Pack right away and take out the Invictus® PU cleaner to eliminate all traces of the installing. We advise you to also use Invictus® Floor Mat to apply an extra matt anti-slip protective finish.

Daily cleaning

The Invictus® Starter Pack is ideal for daily cleaning. When mopping the floor – remember, it is waterproof –, make sure to dilute some Invictus® PU Cleaner in the water. It will remove all traces of daily family life, like dirt and shoe marks, without leaving any residue. To quickly refresh your floor, use diluted Invictus® Floor Mat.


Tips & tricks

With Scratchmaster®, there's little risk of scratching your Invictus® floor. Still, you can further minimize the risk: fit your furniture and chairs with the gliders available in the Starter Pack, and lift instead of dragging when moving furniture. To avoid staining – even if unlikely – it's a good idea to wipe away spills as soon as they happen.


LAYING PATTERNS




Wood block




Random lay




Uniform block




Brick formation




Deck formation



Herringbone



Brick bond




NEED MORE INSPIRATION?

FOLLOW US ON SOCIAL MEDIA

We're excited to bring the Invictus® experience to your screens. Join our community of over 7,000 Invictus® fans and follow us on social media. We share the latest news, exciting product launches, tips & tricks to maintain your floor, inspiring interiors, behind-the-scenes photos and much more.

FOLLOW US ON SOCIAL MEDIA



JOIN OUR INVICTUS COMMUNITY

Get inspired by our community of Invictus® fans. Visit www.invictus.co.uk/lvt/community

Want to join the Invictus® community? Tag @invictuscarpetflooring in your Invictus® luxury vinyl flooring photo on Instagram and use #invictuscarpetflooring for a chance to get featured! Don't have Instagram? Mail your photo to info@invictus.co.uk.



@thisstyle_rocks



@wooltoncarpetcentre



#invictuscarpetflooring

www.invictus.co.uk

TRY OUR
NEW
ROOM
VISUALISER



Always a trailblazer when it comes to branding, **Associated Weavers** brings the Invictus® experience onto every desktop or mobile screen via social media.

Stay up-to-date & follow the official Invictus® social media accounts and join our community of over 7,000 Invictus® fans!

We share the latest product launches, tips & tricks to maintain luxury vinyl flooring, inspiring room-shots, behind-the-scenes photos and many more.

Make your project come to life with the help of the Invictus® room visualiser! Take a photo with your phone or upload your 3D render to discover the many options Invictus® Luxury Vinyl Flooring has to offer.



#invictuscarpetflooring



#invictuscarpetflooring



THE FLOORING INNOVATION AWARDS 2020
GOLD WINNER • The Best of the Best • MARKETING CATEGORY



INVICTUS® LUXURY VINYL FLOOR SHOP-IN-SHOP

**WANT TO EXPERIENCE
INVICTUS® FIRSTHAND?
YOUR PREFERRED
INVICTUS® RETAILER IS
THERE FOR YOU.**

Your preferred Invictus® retailer will gladly advise you on the Invictus® luxury vinyl flooring that best fits your style and your home.

With the award-winning interactive Invictus® display you're in for an exceptional instore experience. Browse through the large-scale samples of all design options of Invictus® Primus, Maximus and Maximus Click.

Scan your favourites, view them in various room settings, discover matching accessories and take home a few samples of your choice.


For a set of samples delivered directly to your home, please visit www.invictus.co.uk



INVICTUS® LUXURY VINYL FLOOR SHOP LOCATOR



Find your nearest Invictus Authorized Dealer



**FOR A PREVIEW OF THE
IN-STORE EXPERIENCE THAT
AWAITS YOU, FOLLOW THE
HIGHLANDER IN OUR FILM:**

The Invictus® experience starts at home. Go online, preselect your favourite floors in the Room Visualiser and generate a unique code. Take the code with you to the shop, where your preferred Invictus® retailer will instantly recall your selection to the Invictus® display's screen to make your in-store experience even more exclusive. To find your preferred Invictus® retailer, use our online shop locator.




Scan your favourites and bring them alive on screen



Explore through the user-friendly touch screen



Examine in the illuminated sample presentation area





YOUR INVICTUS® LUXURY VINYL FLOOR COMES WITH WARRANTIES



Invictus® Primus luxury vinyl flooring delivers a great performance. It therefore comes with a 20-year warranty for residential use. To benefit from it, all you must do is register your purchase online and follow the installing and maintenance instructions. For terms and conditions regarding Invictus® warranties, please visit www.invictus.co.uk.



Invictus® Maximus and Maximus Click luxury vinyl flooring are sure to deliver an extraordinary performance for many years to come. They therefore come with a 25-year warranty for residential use. To benefit from it, all you must do is register your purchase online and follow the installing and maintenance instructions. For terms and conditions regarding Invictus® warranties, please visit www.invictus.co.uk.



Invictus® Maximus and Maximus Click luxury vinyl flooring are sure to deliver an extraordinary performance for many years to come. They therefore come with a 15-year warranty for commercial use such as care, hospitality, office and retail. To benefit from it, all you must do is register your purchase online and follow the installing and maintenance instructions. For terms and conditions regarding Invictus® warranties, please visit www.invictus.co.uk.



Specification

Thickness	EN ISO 24346	2.00 mm
Wearlayer	EN ISO 24340	0.30 mm
Weight per sqm	EN ISO 23997	3550 g/m ²
Surface PUR coating		Scratchmaster® top layer
Classification	EN ISO 10874	23 Domestic Heavy - 31 Commercial Light

Performance

Reaction to fire	EN 13501-1	Bfl-S1
Slip resistance	EN 13893	DS
Slip resistance (dynamic coefficient of friction)	DIN 51130	R10
Thermal resistance (R value)	EN 12664	0.027 (m ² .K)/W
Underfloor heating	EN ISO 12524	Yes, max. 27° C
Electrostatic performance (antistatic)	EN 1815	< 2 kV
Residual indentation	EN ISO 24343-1	<0.1 mm
Dimensional stability	EN ISO 23999	≤ 0.15%
Dimensional stability (curling)	EN ISO 23999	pass
Castor chair resistance	EN ISO 4918	pass, Type W
Colour fastness	EN ISO 105-B02	>6
Impact sound insulation	EN ISO 717-2 (ΔLw)	3dB
Chemical / Stain resistance	EN ISO 26987	pass
Abrasion resistance	EN ISO 660-1	class T
French VOC regulation	ISO 16000	A+
Indoor AIR quality	ISO 16000	Greenguard GOLD
Indoor AIR quality		Floorscore
Content of pentachlorophenol		PCP under detection limit
Formaldehyde emissions	EN ISO 717-1 (28 days test)	NA HCHO (has not been added)
Phthalate free		Yes, biobased
CE marking		EN 14041:2011

Packaging

		Size plank / tile	Pieces / carton
Size and packaging wood	EN ISO 24342	178x1219 mm (7"x48")	17 planks / carton = 3.69 m ² (39.67 ft ²) / carton
Size and packaging stone	EN ISO 24342	305x610 mm (12"x24")	20 tiles / carton = 3.72 m ² (40 ft ²) / carton
Size and packaging parquet	EN ISO 24342	102x406mm (4"x16")	36 planks / carton = 1.49m ² (16ft ²)/carton

Warranty

Warranty	20 years Residential Use
----------	--------------------------

The technical data is correct at the time of printing, 02/2021

20 year warranty

family friendly

pet friendly

water proof

easy maintenance

silent underfoot

underfloor heating

100% recyclable and reusable



Specification

Thickness	EN ISO 24346	2.50 mm
Wearlayer	EN ISO 24340	0.55 mm
Weight per sqm	EN ISO 23997	4310 g/m ²
Surface PUR coating		Scratchmaster® top layer
Classification	EN ISO 10874	23 Domestic Heavy - 33 Commercial Heavy - 42 Industrial General

Performance

Reaction to fire	EN 13501-1	Bfl-S1
Slip resistance	EN 13893	DS
Slip resistance (dynamic coefficient of friction)	DIN 51130	R10
Thermal resistance (R value)	EN 12664	0.028 (m ² .K)/W
Underfloor heating	EN ISO 12524	Yes, max. 27°C
Electrostatic performance (antistatic)	EN 1815	< 2 kV
Residual indentation	EN ISO 24343-1	<0.1 mm
Dimensional stability	EN ISO 23999	≤ 0.15%
Dimensional stability (curling)	EN ISO 23999	pass
Castor chair resistance	EN ISO 4918	pass, Type W
Colour fastness	EN ISO 105-B02	>6
Impact sound insulation	EN ISO 717-2 (ΔLw)	3dB
Chemical / Stain resistance	EN ISO 26987	pass
Abrasion resistance	EN ISO 660-1	class T
Content of pentachlorophenol		PCP under detection limit
Formaldehyde emissions	EN ISO 717-1 (28 days test)	NA HCHO (has not been added)
CE marking		EN 14041:2011

Packaging

		Size plank / tile	Pieces / carton
Size and packaging wood	EN ISO 24342	178x1219 mm (7"x48")	15 planks / carton = 3.25 m ² (35 ft ²) / carton
Size and packaging wood XL plank	EN ISO 24342	229x1517 mm (9"x59.72")	10 planks / carton = 3.47 m ² (37.33 ft ²) / carton
Size and packaging wood parquet	EN ISO 24342	102x406 mm (4"x16")	34 planks / carton = 1.40 m ² (15.11 ft ²) / carton
Size and packaging stone	EN ISO 24342	305x610 mm (12"x24")	18 tiles / carton = 3.34 m ² (36 ft ²) / carton
Size and packaging stone	EN ISO 24342	457x457 mm (18"x18")	16 tiles / carton = 3.34 m ² (36 ft ²) / carton
Size and packaging stone	EN ISO 24342	500x500 mm (19.69"x19.69")	14 tiles / carton = 3.50 m ² (37.67 ft ²) / carton
Size and packaging stone	EN ISO 24342	229x229 mm (9"x9")	40 tiles / carton = 2.09 m ² (22.50 ft ²) / carton
Size and packaging stone	EN ISO 24342	457x914 mm (18"x36")	8 tiles / carton = 3.34 m ² (36 ft ²) / carton

Warranty

Warranty	25 years Residential / 15 years Commercial
----------	--

The technical data is correct at the time of printing, 02/2021



Specification

Description	Rigid core SPC with sound insulating underlay attached	
Thickness	EN ISO 24346	6.00 mm
Wearlayer	EN ISO 24340	0.55 mm
Weight per sqm	EN ISO 23997	9820 g/m ²
Surface PUR coating	Scratchmaster® top layer	
Locking System	Unilin's Unipush® click technology	
Classification	EN ISO 10874	23 Domestic Heavy - 33 Commercial Heavy

Performance

Reaction to fire	EN 13501-1	Bfl-S1
Slip resistance	EN 13893	DS
Slip resistance (dynamic coefficient of friction)	DIN 51130	R10
Thermal resistance (R value)	EN 12664	0.048 (m ² .K)/W
Underfloor heating	EN ISO 12524	Yes, max. 27°C
Electrostatic performance (antistatic)	EN 1815	< 2 kV
Residual indentation	EN ISO 24343-1	<0.1 mm
Dimensional stability	EN ISO 23999	≤ 0.15%
Dimensional stability (curling)	EN ISO 23999	pass
Castor chair resistance	EN ISO 4918	pass, Type W
Colour fastness	EN ISO 105-B02	>6
Impact sound insulation	EN ISO 717-2 (ΔLw)	20dB
Chemical / Stain resistance	EN ISO 26987	pass
Abrasion resistance	EN ISO 660-1	class T
French VOC regulation	ISO 16000	A+
Indoor AIR quality	ISO 16000	Greenguard GOLD
Indoor AIR quality		Floorscore
Content of pentachlorophenol		PCP under detection limit
Formaldehyde emissions	EN ISO 717-1 (28 days test)	NA HCHO (has not been added)
Phthalate free		Yes, biobased
CE marking		EN 14041:2011

Packaging

		Size plank / tile	Pieces / carton
Size and packaging wood	EN ISO 24342	178x1213 mm (7"x47.75")	8 planks / carton = 1.725 m ² (18.57 ft ²) / carton
Size and packaging stone	EN ISO 24342	298x603 mm (11.75"x23.75")	8 tiles / carton = 1.440 m ² (15.503 ft ²) / carton

Warranty

Warranty	25 years Residential - 15 years Commercial
----------	--

The technical data is correct at the time of printing, 02/2021

-
-
-
-
-
-
-
-
-
-
-
-
-

INVICTUS MAXIMUS DRYBACK - SLIP RESISTANCE Pendulum test values - BS 7976-2

TYPE	DESIGN	DRY		WET	
		Lowest Test Value	Slip Risk Class	Lowest Test Value	Slip Risk Class
WOOD	DESIGNERS PARQUET	61	LOW	31	MODERATE
WOOD	FRENCH OAK	64	LOW	36	LOW
WOOD	HIGHLAND OAK	64	LOW	36	LOW
WOOD	NEW ENGLAND OAK	59	LOW	33	MODERATE
WOOD	NORWEGIAN WOOD	60	LOW	42	LOW
WOOD	TROPICAL FOREST	59	LOW	47	LOW
PARQUET	HIGHLAND OAK	64	LOW	36	LOW
PARQUET	NEW ENGLAND OAK	59	LOW	33	MODERATE
STONE	BELGIAN BLUESTONE	63	LOW	23	HIGH
STONE	BERGAMO	60	LOW	43	LOW
STONE	CONCRETE CRUSH	63	LOW	23	HIGH
STONE	GROOVY GRANITE	60	LOW	32	MODERATE
STONE	HUDSON STONE	62	LOW	37	LOW
STONE	VICTORIAN TREASURE BORDER	63	LOW	23	HIGH
STONE	VICTORIAN TREASURE DECOR	63	LOW	23	HIGH

INVICTUS MAXIMUS (SPC) CLICK - SLIP RESISTANCE Pendulum test values - BS 7976-2

TYPE	DESIGN	DRY		WET	
		Lowest Test Value	Slip Risk Class	Lowest Test Value	Slip Risk Class
WOOD	FRENCH OAK	64	LOW	37	LOW
WOOD	HIGHLAND OAK	64	LOW	37	LOW
WOOD	NORWEGIAN WOOD	60	LOW	42	LOW
STONE	HUDSON STONE	62	LOW	37	LOW
STONE	BERGAMO	60	LOW	43	LOW
STONE	GROOVY GRANITE	64	LOW	33	MODERATE

36+ SLIP RESISTANCE

For your safety, Invictus® comes in a number of 36+ slip resistant planks and tiles.

The Floor Pendulum Test proves if the floor Slip Resistance Values meet the H&S recommended minimum values for commercial flooring in public spaces.

36+

ultra slip resistant

LIGHT REFLECTION VALUE BS.8493:2008+A1:2010.

DESIGN	LRV	DESIGN	LRV
DESIGNERS PARQUET DUCHESS	27.4	BELGIAN BLUESTONE DOLPHIN	25.9
DESIGNERS PARQUET PRINCESS	36.3	BELGIAN BLUESTONE MIDNIGHT	11.8
DESIGNERS PARQUET QUEEN	21.3	BERGAMO CLOUD	33.5
FRENCH OAK ALMOND	20.7	CONCRETE CRUSH CHARCOAL	10.8
FRENCH OAK BURNT	13.9	CONCRETE CRUSH SMOKE	28.3
FRENCH OAK DESERT	26.8	GROOVY GRANITE DUNE	38.6
FRENCH OAK LINEN	27.9	GROOVY GRANITE LAVA	14.5
FRENCH OAK POLAR	47.1	GROOVY GRANITE SHADOW	30.4
FRENCH OAK STORM	29.8	GROOVY GRANITE STEEL	30.1
FRENCH OAK SUN	23.5	HUDSON STONE FLINT	21.8
HIGHLAND OAK CANYON	23.4	HUDSON STONE GRAPHITE	12.5
HIGHLAND OAK CHOCOLATE	11.5	HUDSON STONE SILVER	34.3
HIGHLAND OAK CLASSIC	23.8	PURE MARBLE SNOW	76.3
HIGHLAND OAK EBONY	13.5	SANDSTONE NERO	15.7
HIGHLAND OAK FROSTED	25.6	SANDSTONE SAVANNAH	31.8
HIGHLAND OAK ROASTED	15.3	TERRAZZO TAUPE	29.8
NEW ENGLAND OAK DUSK	18.5	YORK STONE POWDER	48.9
NEW ENGLAND OAK MISTY	26.4	VICTORIAN TREASURE DECO CHARCOAL	35.0
NEW ENGLAND OAK SAND	22.1	VICTORIAN TREASURE DECO SMOKE	44.6
NEW ENGLAND OAK TOFFEE	12.0		
NORWEGIAN WOOD ARCTIC	40.6		
NORWEGIAN WOOD BARREL	9.9		
NORWEGIAN WOOD FJORD	23.6		
NORWEGIAN WOOD THUNDER	15.2		
SHERWOOD OAK FOSSIL	37.69		
SHERWOOD OAK MINK	16.3		
SHERWOOD OAK SHELL	29.3		
ROYAL OAK BLONDE	26.1		
ROYAL OAK DOVE	25.9		
ROYAL OAK EDEN	45.1		
ROYAL OAK MOCCA	9.5		
ROYAL OAK NORDIC	25.4		
ROYAL OAK TRADITIONAL	18.7		
TROPICAL FOREST ARUBA	42.6		
TROPICAL FOREST HAVANA	17.3		
TROPICAL FOREST PERU	27.3		
VINTAGE OAK CAFÉ AU LAIT	28.5		

WHAT IS LIGHT REFLECTANCE VALUE?

LRV is a universal value for 'contrast'. It measures the proportion of useful light reflected by a coloured object. It represents a relative light and darkness value rather than an actual colour. Therefore, dissimilar colours could have the same LRV.

LRV is measured on a scale of 0 to 100, 0 being perfect absorbing black and 100 being perfect reflecting white (in reality you never find these perfect objects - a bright white would typically have a result of an LRV of 85).

Overview strengths



With its ultra-strong coating and highly efficient top layer, Invictus® luxury vinyl flooring offers outperforming wear protection. The Scratchmaster® top layer will make your luxury vinyl floor withstand busy family life with kids and pets.



Invictus® is the pet friendly flooring par excellence, operating as a barrier against stains and fine scratches from our furry friends.



Invictus® Maximus and Maximus Click luxury vinyl flooring deliver an extraordinary performance and come with a 15-year warranty for commercial use. For more information, register online at www.invictus.co.uk.



Because it's waterproof, Invictus® luxury vinyl flooring is perfectly suited for your bathroom, kitchen and hall. And for any other room, naturally.



Invictus® Maximus and Maximus Click deliver an extraordinary performance and benefit from a 25-year warranty. For more information, register online at www.invictus.co.uk.



Caring for your Invictus® luxury vinyl floor is as easy as it gets: a damp mop will do. And for daily maintenance, the Invictus® Starter Pack contains all you need.



Invictus® Primus performs so well, that it comes with a 20-year warranty. For more information, register online at www.invictus.co.uk.



Whether on socks or in shoes, you will always walk silently on an Invictus® luxury vinyl floor. It indeed is incredibly silent underfoot.



Invictus® luxury vinyl flooring is a family's best companion. It's wear-, scratch- & stain-resistant, and requires little maintenance.



What's better than unwinding in the tranquility of your own home? Your Invictus® luxury vinyl floor contributes to a silent and relaxing environment.



Invictus® luxury vinyl flooring and underfloor heating go together well. With the right installing guidelines, you'll be enjoying a warm feel underfoot in no time.



Grant your Invictus® Maximus Click luxury vinyl floor a high-quality finish by adding a 100% matching scotia. It will both cover the expansion gap and perfectly match the colour and design of your floor.



Designs so lifelike, they will have you look twice. From natural wood look to striking stone tile pattern, there's an Invictus® luxury vinyl floor for all decorating styles.



No subfloor preparation is needed before installing your Invictus® Maximus Click floor. The rigid character of the planks and tiles will even out most imperfections.



Invictus® luxury vinyl flooring and broadloom carpet are a perfect match. When great comfort meets great performance, it will transform your home.



In register embossing follows the wood design of your Invictus® Maximus or Maximus Click floor, thus giving it depth and an exceptionally realistic look.



Aesthetic and practical, a bevel contributes to the realistic look of the wood or stone design of your Invictus® floor, and levels out minor installing imperfections.



The extra large design results in minimal pattern repetition, giving a truly unique & natural look to any space.



Little preparation, quick installation and no waiting time afterwards: Invictus® Maximus Click luxury vinyl flooring is the easy way to give your home a complete make-over. The ideal solution for your renovation project!



The XL planks make the best of the attractive pattern. The dimensions of the planks increase the feeling of grandeur and will not fail to impress.



Invictus® Luxury Vinyl Flooring products are 100% recyclable and reusable. They can be part of vinyl flooring take-back programmes with the goal to recycle them into new flooring or other useful products such as rubber hoses, car mats and speed bumps.



For your safety, Invictus® comes in a number of 36+ slip resistant planks and tiles. The Floor Pendulum Test proves if the floor Slip Resistance Values meet the H&S recommended minimum values for commercial flooring in public spaces.

THE ESTABLISHED
CARPET BRAND
INVICTUS® NOW
BRINGS YOU
LUXURY VINYL
FLOORING

INVICTUS®

Great carpet, Invincible comfort

Since its launch in 2015, Invictus® has been the ultimate reference in the UK market for comfortable broadloom carpet. With its dense pile, Invictus® carpet will make you prefer the carpet to the sofa.

The makers of Invictus® carpet now present Invictus® luxury vinyl flooring. With the same attention to quality, the same eye for exclusive designs, and a unique performance level, Invictus® luxury vinyl flooring is the perfect match to Invictus® carpet.

Invictus® carpet and Invictus®
luxury vinyl flooring:
a perfect match



Who said you should pick only one flooring for throughout the house? There really is no need to battle it out with your housemates. Luxury vinyl flooring and broadloom carpet are a perfect match. And the best part? In the Invictus® collection, you'll find both!

For one-stop-shopping of both luxury vinyl flooring and broadloom carpet, Invictus® is the way to go. We've meticulously selected a series of broadloom carpet to perfectly match your new luxury vinyl floor. From kitchen to living room, from bathroom to bedroom ... you may step onto a different floor, but you'll keep walking on the same high quality.


MATCHING CARPETS

	CARPET MAGNIFICUS / CENTURION					CARPET SEVERUS / SEPTIMUS															
	09	30	31	35	37	90	93	95	97	98	03	31	33	36	37	38	91	92	94	95	
Belgian Bluestone Dolphin																					
Belgian Bluestone Midnight																					
Bergamo Cloud																					
Concrete Crush Charcoal																					
Concrete Crush Smoke																					
Designers Parquet Duchess																					
Designers Parquet Princess																					
Designers Parquet Queen																					
French Oak Almond																					
French Oak Burnt																					
French Oak Desert																					
French Oak Linen																					
French Oak Polar																					
French Oak Storm																					
French Oak Sun																					
Groovy Granite Dune																					
Groovy Granite Lava																					
Groovy Granite Shadow																					
Groovy Granite Steel																					
Highland Oak Ash																					
Highland Oak Canyon																					
Highland Oak Chocolate																					
Highland Oak Classic																					
Highland Oak Ebony																					
Highland Oak Frosted																					
Highland Oak Roasted																					
Hudson Stone Flint																					
Hudson Stone Graphite																					
Hudson Stone Silver																					
New England Oak Dusk																					
New England Oak Misty																					
New England Oak Sand																					
New England Oak Toffee																					
Norwegian Wood Arctic																					
Norwegian Wood Barrel																					
Norwegian Wood Fjord																					
Norwegian Wood Thunder																					
Pure Marble Snow																					
Royal Oak Blonde																					
Royal Oak Dove																					
Royal Oak Eden																					
Royal Oak Mocca																					
Royal Oak Nordic																					
Royal Oak Traditional																					
Sandstone Nero																					
Sandstone Savannah																					
Sherwood Oak Fossil																					
Sherwood Oak Mink																					
Sherwood Oak Shell																					
Terrazzo Time Taupe																					
Tropical Forest Aruba																					
Tropical Forest Havana																					
Tropical Forest Peru																					
Victorian Treasure - Border Charcoal																					
Victorian Treasure - Border Smoke																					
Victorian Treasure - Decor Charcoal																					
Victorian Treasure - Decor Smoke																					
Vintage Oak Café au Lait																					
York Stone Powder																					


MAGNIFICUS




CENTURION



SEVERUS



SEPTIMUS





About Associated Weavers

Associated Weavers has been present in the UK since 1964. Always a trailblazer, the company has been at the forefront of broadloom carpet's finest innovations. Inspired by the tremendous success of Invictus® carpet, Associated Weavers proudly presents Invictus® luxury vinyl flooring.

From its headquarters in Halifax, Associated Weavers over the years has built strong and lasting relationships with its partners nationwide. A passion for flooring, thorough product knowledge and an eye for great interior design are the strengths of Associated Weavers' 40-strong dedicated UK sales team.

A UK brand
since 1964





v04-2021

